05-Feb-25

To

M/s. NICE DENIM MILLS LIMITED,
DHAKA,
BANGLADESH.

[Proposal No: 05.Feb.2025/WTT-0852/BAN/NS-CRS/3.6M/R0/TCP].

Dear Sir,

WTT International Private Limited (WTT) is pleased to provide M/s. MOMIN TEXTILE MILLS with the **Techno Commercial Proposal** for supply of engineering & materials for **Color Removal System of capacity 3600 M^3/Day.** In developing this offer WTT worked with you in an effort to understand your project and business needs. The attached proposal outlines the solutions we feel will best meet these objectives.

We greatly appreciate your consideration of WTT for this project. Our measure of success is how well we deliver solutions that help our client to meet their critical business objectives. We hope to have the opportunity to demonstrate this with your good selves.

Yours Sincerely,

D. Venkatesh
Managing Director

S.NO	DESCRIPTION	DATE	PREPARED	APPROVED
1.	Techno Commercial Proposal – "Color removal system of capacity 3600 M^3/DAY"	05-Feb-25	SB - GET AR - AGM	DV - MD

CONFIDENTIALITY

All details, specifications, drawings, images, and all other information submitted by us are only intended to the person/organization to which it is addressed and contains proprietary, confidential and or privileged material. Any review, retransmission, dissemination, or other use of, or of taking action in reliance upon this information by person or entities other than the intended recipient is prohibited. All or part information contained in the document is solely intended to the person or entity addresses and sharing this document in part or in whole is prohibited.

WE FEEL DELIGHTED TO PRESENT OUR PATENTED SYSTEMS

Award For Excellence in Water Management

CII (Confederation of Indian Industry) *awarded*
WTT International *with the prestigious*

"Excellence in Water Management Award"

recognizing the advanced water treatment technologies
innovated by ***WTT International***
As a part of Industrial Water / Waste Management competition 2023

CONTENT

1. TECHNICAL AND ENGINEERING DETAILS 5
1.1. BASIS OF DESIGN 5
1.2. INFLUENT FLOW DATA 5
1.3. PROCESS COMPATIBILITY 5
2. DESIGN SYSTEM CHOSEN 5
3. EQUIPMENT DETAILS FOR PROPOSED SYSTEMS 6
3.1. COLOR REMOVAL SYSTEM 6
4. EQUIPMENT SCOPE OF SUPPLY – BY WTT 6
5. SCOPE OF SUPPLY & INSTALLATION - BY CLIENT 9
6. PRICING DETAIL 12
7. COMMERCIAL TERMS AND CONDITIONS 13
7.1. TAXES 13
7.2. INVOICING AND PAYMENT TERMS 13
7.3. EQUIPMENT SHIPMENT 13
7.4. FORCE MAJEURE 14
7.5. PRICING NOTES 14
8. CLIENT SCOPE OF SUPPLY 14
8.1. SAFETY AND ENVIRONMENTAL 14
8.2. JOBSITE AND INSTALLATION REVIEW 15
8.3. START-UP AND COMMISSIONING 16
8.4. FACILITY MANAGEMENT 17
8.5. CONDITIONAL OFFERING 17
9. APPENDIX 18
9.1. APPENDIX A: CLARIFICATIONS 18
9.2. APPENDIX B: ACCEPTANCE 18
9.3. APPENDIX C: WARRANTY 19

1. Technical And Engineering Details

1.1. Basis Of Design

- ✓ *Color removal system proposed involves utilizing chlorine gas to effectively eliminate color from the water*

The following sections summarize the treatment processes, the major system components, the main system design parameters and design outputs as well as design details of system components. This section does not define scope of supply. Scope delineation is covered under section 3.

1.2. Influent Flow Data

PARAMETER	VALUE	UNIT
COLOR REMOVAL SYSTEM FEED FLOW RATE	3600	M^3/Day

1.3. Process Compatibility

1. The incoming raw wastewater shall not contain any substance incompatible with the MOC of the Equipment supplied & inhibitory substances that sufficiently affect operation of any of the system.

2. Design System Chosen

S.NO	PROCESS	CAPACITY (M^3/Day)
1.	COLOR REMOVAL SYSTEM	3600

***System capacities mentioned above are based on Color removal system influent flow Rate and the Actual capacities may vary.**

3. Equipment Details for Proposed Systems

3.1. Color Removal System

Color removal using chlorine dioxide gas involves applying chlorine dioxide, a strong oxidizing agent, to degrade color-causing compounds in water. It efficiently removes organic dyes and pollutants through oxidation, making it suitable for industrial and wastewater treatment processes. It also acts as a disinfection system and the excess chlorine will get evaporated into the atmosphere.

4. Equipment Scope of Supply – BY WTT

PLANT EQUIPMENT LIST			
A	**COLOR REMOVAL SYSTEM**		**3600 M^3/Day**
S.NO	**DESCRIPTION**	**SPECIFICATION**	**QUANTITY**
	COLOR REMOVAL SYSTEM	CHLORINATOR	1W + 1S
		ROTAMETER	2 No's
		FLOOR-MOUNTED FRP CABINET	2 No's
		DIFFERENTIAL PRESSURE REGULATOR	2 No's
		INJECTOR	2 No's
		EQUIPMENT FRAME AND SUPPORTS	2 No's
		AUTO CHANGEOVER VALVE GAS LINE	1 No
		AUTO SHUT OFF VALVE GAS LINE	2 No's
		ELECTRICAL CONTROL PANEL	1 No
		EXPANSION CHAMBER WITH ISOLATION VALVE	1 No
		CHLORINATOR BOOSTER PUMP	2W
		PUMP TYPE	SURFACE MOUNTED
		PUMP MOC	SS316
		RUPTURE DISC	1 No

		CHLORINE STEAM HEATED EVAPORATOR	1 No
		TEMPERATURE GAUGE FOR STEAM CHAMBER	1 No
		TEMPERATURE CONTROLLER LOW AND HIGH CUTOFF	1 No
		FRP GAS FULL HOOD	6 No's
		BLOWER MOTOR ASSEMBLY	2 No's
		FRP ABSORPTION TOWER	1 No
		ABSORPTION TANK	1 No
		PP CIRCULATION PUMP & MOTOR ASSEMBLY	2 No's
		TANK LEVEL INDICATOR	2 No's
		CHLORINE GAS LEAK DETECTOR WITH DUAL SENSOR AND ALARM	2 Set
		SELF-CONTAINED BREATHING APPARATUS 45 MIN	2 No's
		EMERGENCY EYE WASH AND SHOWER	1 No
		PROTECTIVE CLOTHING – (SAFETY PVC SUIT WITH FULL FACE MASK, PVC GLOVES AND GUM BOOT	2 No's
		GAS MASK WITH CANISTER	2 No's
		TONNER ROLLER SUPPORTS	6 Set
		LIFTING BEAM WITH ADJUSTABLE HOOKS	1 No
		DIFFUSER	1 LOT
		DIFFUSER SIZE	11"
		DIFFUSER TYPE	FINE BUBBLE
		DIFFUSER PORES SIZE	80 MICRON
		DIFFUSER MOC	PP-GF disc with SILICON membrane
		DIFFUSER GRID	1 LOT
		DIFFUSER GRID PIPING MOC	SS316L

W – Working; S – Standby; SS – Store Standby

Specification and quantity details mentioned above are preliminary and may be revised to optimize the performance of the system.

OTHER GENERAL ITEMS IN WTT's SCOPE:

- *Piping in SS, CPVC, UPVC and its associated items*
- *All other related valves and puddle flanges required*
- *Power cable and control cable within the electrical panel*
- *Power cable and control cable from electrical panel to proposed equipment*
- *General layout & civil detailed drawing for proposed system*
- *Booster pumps should be provided with flow rate and discharge head as per the site Availability and site requirement.*
- *Tap-Off with Tap-Off-Flange along with isolation valve in mainline (effluent water source) for make-up waterline*
- *Make-up effluent water line shall be provided up to chlorination room/circulation pump, along with necessary valves, Instruments, Strainers and fittings, as required, as applicable. We can provide the same.*
- *Motive effluent water line shall be provided inside skid along with valves and fittings*
- *Chlorine solution line (up to 12 meters) from injector outlet shell, as per the site requirement, Material of pipes and fittings UPVC/HDPE pressure rating 10 BAR size 80 NB. All materials and equipment prescribe to the standards set by chlorine Institute Inc.U.S.A. and IS: 10553 (part- 1&2)1983.*
- *PLC Based Automation System should be provided by as with interlocks for the following*
    - *Automatic shut-off of chlorine supply, In case of power failure, Low water pressure in injector inlet or chlorine gas leakage. Automatic start chlorine leak Absorption system in case of chlorine gas leakage.*

OTHER TECHNICAL DETAILS FOR CLIENT REFERENCE:

- *Chlorinator capacity and quantity is 60 kg/hr (1W + 1S)*
- *Effluent Water flow at EACH working injector Inlet is 30 m^3/hr*
- *Make – up Effluent water pipeline size is 100 NB*
- *Motive water Effluent pipeline size is 80 NB*
- *Chlorine solution pipeline size- individual is 80 NB*
- *Effluent Water pressure required at injector inlet for assumed min 0.5 back pressure is 4.5 kg/cm^2*

5. Scope Of Supply & Installation - By Client

- Installation of supplied Equipment
- Transfer of Effluent up to proposed Gas chlorination system inlet
- Existing circulation pump to be utilized
- Wiring between Instruments control panel inside the chlorination Room
- Electrical works for chlorination system
    - Power supply @ 415 V, 50 Hz, 3 phase, 4 wire and / or 230V ± 10%,50Hz ± 5% single phase to be provided by the client to each panel MCC power cabling power cable, cable trenches, cable trays, UPS shall be provided by client if and as applicable, wiring between Instruments control panel inside the chlorination Room.
- Civil work is in client scope however we shall provide civil foundation drawings, as applicable, after placement of P.O. for facilitating installation works.
- Auto chlorine gas tonner leak absorption system
    - The scope of work includes supply of chlorine gas Leakage Absorption package system. Supply would be as per our attached List of items of supply only.
    - Pipeline for process water for cleaning of the Absorption Tank and for dilution of Absorbent chemical to be provided by the Clients along with a valve size 50 NB.
    - Chemicals for neutralization to be provide by the client (caustic soda Lye and sodium thiosulphate). Please note that addition of Sodium-thio-sulphate helps

to quicken the neutralization. The neutralization is complete in all respects and disposal of the absorbed chlorine is safe as it does not precipitate chlorine in Air.

- The absorption tank and tower should be close and Adjacent to Tonners/Cylinder Storage Room/chlorination plant Room to minimize long chlorine-air suction pipeline to Blower and absorption Tower.
- I-Beams/Monorail to be provided by the Client for movement of manual or Electric Hoists with push pull Trolley (Tonner Handling-Clients Scope) All indication/Alarms will be confined to the chlorination Room if the same is required in other places, it is in Clients Scope.
- Instrument Air and its Air piping will be supplied by the Client at pressure of 5-6 bar in GI/copper/SS pipe of minimum 20 NB size and/or Copper or PU Hose up to our supplied instruments. Or else. Exclusive compressor with airline. Instrument Air for cleaning or purging of pipeline shall be provided by the Client at pressure of 6-8 bar.
- Chemicals for NEUTRALIZATION / Absorption, Water Testing chemicals / Kits are to be provided by the Clients Scope.
- Raw / Permeate water supply for whole plant
- Compressed air with airline for pneumatic valves
- Air conditioning Systems for Panel room & Personal Computers
- Incomer cable and its connections with WTT supplied electrical panel
- Two Separate & Distinct Earthing for all individual equipment & panel
- Instruments/Electronics Earthing & Safety/Protective Earthing shall be provided for individual Instruments, Motor/Pump & Other Electrical Equipment
- Input power to individual WTT supplied electrical panel
- All civil related works, civil structural drawings, underground piping & piping for electrical cabling during civil works
- All loading & unloading @ site
- All excavation works related with pipe and cables laying
- Electrical cable & stabilized power supply until WTT panel's, Internal Individual Earthing as per requirement
- Utilities like Power, Steam, Welding gas, Hot water etc., if Required
- Chemical supply for proposed plant

- Separate panel, wiring with fans & lights for whole plant & its power supply
- Pre-Shipment Inspection requested by the local authorities
- All license fees and / or custom duties
- Installation consumables (such as welding electrodes, cutting disk and others)
- Supply and assembly of all drainage lines for rain water, sewers, etc
- Any construction approval from local Authorities
- Supply of any hoisting and/or laying equipment (cranes forklift, etc.) both truck mounted or not
- Construction of site fencing/railing
- Protection for all field instruments, local switches, motors, etc.,
- Safety handrails for all tanks, safety items like life buoy rings, eye washer, life-jackets, etc
- Removal of all residual debris after construction and thorough cleaning of all tanks before plant start-up
- General spares for supplied equipment
- Any further item not described in our offer

6. Pricing Detail

PRICE FOR PROPOSED SYSTEMS		
S.NO	**SYSTEM / EQUIPMENT - 1680 M^3/Day**	**PRICE IN USD**
1.	**COLOR REMOVAL SYSTEM**	**$ 210,831**
TOTAL PRICE FOR PROPOSED SYSTEMS		**$ 210,831**

- Pricing provided herein does not include any duties and taxes
- Pricing provided herein is on **EX-Works** basis & does not include the freight/insurance charges
- Supervision of erection and commissioning of WTT supplied system shall be extra
- To and Fro Air transport, Local Transport, Food, Accommodation Provided by Client Scope
- Payment/commercial terms & conditions as per WTT's General Terms & Conditions of sale
- Price valid for 15 days from the date of proposal due to market volatility

7. Commercial Terms and Conditions

7.1. Taxes

Taxes and Duties shall be extra as applicable. Pricing provided herein does not include any taxes of destination country.

If Tax Exemption is applicable, customer has to provide a copy to WTT of any applicable tax exemption certificates as issued by an approved taxation authority for the specific project location. Without an approved tax exemption certificate received by WTT all submitted invoices will include applicable tax. However we reserve the right to revise our price in case of tax exemption.

7.2. Invoicing and Payment Terms

The pricing quoted in this proposal is based on the following payment terms, in principally agreed.

(1) 70% of the total amount shall be paid as interest free Advances along with technically and commercially clear purchase Order.

(2) 30% of the total amount shall be paid Against Performa Invoice

Equipment shipment is contingent on receipt of earlier milestone payments.

7.3. Equipment Shipment

Client and WTT will arrange a kick off meeting after contract acceptance to develop firm shipment schedule. This estimated delivery schedule assumes no more than 1 week for Client review of submittal drawings. Any delays in Client approvals or requested changes may result in additional charges and/or a delay to the schedule.

Material supply for the proposed plant in 5 - 6 months (approx.) is expected. The delivery schedule excludes the months of August & December, the delivery schedule is subject to review and adjustment. Partial shipments are allowed. In case of modifications to the volume of the supply after the emission of the order confirmation, WTT reserves the right to modify the delivery time and the agreed price.

7.4. FORCE MAJEURE

Please be advised that force majeure is applicable to the quotation provided. The unforeseen and uncontrollable events as defined in our terms and conditions, such as natural disasters, wars or pandemics & other events that prevent the parties from fulfilling their contractual commitments have occurred, impacting our ability to honor the terms outlined in this quotation. We will diligently review the situation and promptly communicate any necessary adjustments or potential delays in fulfilling the quoted services or products in compliance with the force majeure provisions outlined in our agreement.

7.5. PRICING NOTES

All prices quoted are in **USD**. Any applicable tax of destination country is not included. Client will pay all applicable Local, State / Provincial, or Federal taxes & Duties. WTT may manufacture and source the Equipment and any part thereof globally in the country or countries of its choosing, provided that the Equipment complies with all of the requirements specified in this Agreement.

The Equipment delivery date, start date, and date of commencement of operations are to be negotiated. Title and risk of loss will transfer upon delivery in accordance with the INCOTERMS 2010. Commercial Terms and Conditions shall be in accordance with WTT's General Terms and Conditions of Sale as included in Appendix.

8. CLIENT SCOPE OF SUPPLY

8.1. SAFETY AND ENVIRONMENTAL

First aid, emergency medical response, eyewash & safety showers in the water treatment area. Chemical spill response, security & fire protection systems as per local codes. Environmental use and discharge permits for all chemicals at Client facility either listed in this document or proposed for use at a later date. Any special permits required for WTT's or Client employees to perform work related to the water treatment system at the facility. All site testing, including soil, ground and surface water, and air emissions, etc. Disposal of all solid & liquid waste from WTT's system including waste materials generated during construction, startup and operation.

Provide appropriate protection of the environment & local community, the health and safety of all workers and visitors at the site and the security of the facility. Provide safety related equipment & services such as site security, fire systems, lifting equipment and its operation, fall protection, adequate floor grating, ventilation, and safe access to equipment & electrical systems areas.

Equipment and trained support personnel for any confined space entry required during equipment installation/startup/commissioning/servicing. For permit-required confined space entry, a qualified rescue team on stand-by and available to respond within 4 minutes of an emergency.

Client will identify and inform WTT's personnel of any hazards present in the work place that could impact the delivery of WTT's scope of supply and agrees to work with WTT to remove, monitor, and control the hazards to a practical level. Client will provide training to WTT's personnel on all relevant & standard company operating procedures and practices for performing work on site.

8.2. JOBSITE AND INSTALLATION REVIEW

Review of WTT's supplied equipment drawings and specifications. All easements, licenses and permits required by governmental or regulatory authorities in Connection with the supply, erection and operation of the system.

Overall plant design, detail drawings of all termination points where WTT's equipment or Materials tie into equipment or materials supplied by others Stamping, signing or Sealing General drawings as per State, or local regulations or codes. All applicable civil design and works, including any building, site preparation, grading, excavations, foundations and trenches and accessories.

All electrical Labor and supplies leading up to jobsite including fittings, conduit, supports, cable trays, wire and hardware, air-conditioning of panels required to appropriately ground / earth the equipment as required for installation and ongoing operations.

All mechanical Labor and supplies leading up to jobsite including interconnecting piping, heat tracing (if required), fittings, conduit, pipe supports, and hardware as required for installation and ongoing operations. All instrumentation and automatic pneumatic valves

including but not limited to; air/sample line tubing, fittings, conduit, supports, isolating valves as required for installation and ongoing operations. Loading, unloading and transportation of equipment, materials required for WTT to perform duties outlined in WTT's Scope of Supply to the jobsite and/or warehouse.

Client will provide all access structures (scaffolding), mechanical lifting equipment (cranes, forklifts, scissor lifts, etc.), suitable site/shelter for placement of the proposed equipment, either inside appropriate housing, or outdoors.

Precaution: electrical equipment including the PLC may require air-conditioned rooms to prevent overheating of sensitive electronic equipment depending on climatic conditions. Bulk chemical storage and tanks, including secondary containment in accordance with local codes. Client will receive, off-load, log, and store all chemical and materials in accordance with Manufacturer's recommendation that are shipped. Compressed instrument air for pneumatic valves instruments and ejector system Equipment anchor bolts, Laboratory services, operating and maintenance personnel during equipment checkout, start-up and operation. Any on-site painting or touch-up painting of equipment supplied. Disposal of any Preservative.

For erection, WTT will ship the accessories such as pipes, bolts, nuts, screws, cables, valves any other equipment or devices in excess quantities than required. This is in order to avoid shortages during the assembly due to damage or any other cause as it is difficult to procure the accessories locally. It is notified that all the shipped accessories during assembly and the excess accessories after commissioning are always remain the properties of WTT. WTT has the authority to retake the same at any period of time, even before and after commissioning. It is client's responsibility to preserve the above-mentioned items till WTT takes back the same.

8.3. START-UP AND COMMISSIONING

Installation & removal of temporary screens on all process lines Flushing and disinfection of all piping and tanks (including process equipment tanks) and verification of removal of all residual debris from construction. Alignments & required materials for rotating equipment MEG testing of all field motor power wiring (as required). Continuity checks for all electrical field wiring as per Installation Checklist, Hydro-testing of all field installed piping.

Supply raw materials, oil/lubricants chemicals and utilities during start-up and operation. Electrical & Mechanical support labor for commissioning activities, loading of membranes, stacks, modules, etc.

8.4. FACILITY MANAGEMENT

Client will provide such warehouse storage space and facilities, as are available at the site, and are reasonably appropriate to store parts, consumables, tools, etc. in accordance with manufacturer's recommendations. Such warehouse storage space will be a segregated area, secured and protected from adverse climate as may reasonably be required. The storage area shall be facilitated with 24 hours lock & key with security and Client will be responsible for risk of loss of WTT's parts while in storage at the site. Client will maintain WTT's parts stored at the site free & clear of any and all liens of Client and lenders, bondholders, contractors & other creditors of any nature.

Client will afford WTT's personnel free access and egress of the facility for all authorized work. Provide workshop facilities/area with roof and stabilized power supply, as is reasonably appropriate to carry out machining/fabrication works.

Provide adequate illumination and emergency lighting for all areas in which the WTT will be executing the scope of supply. Identify a Client project contact person to be available to WTT's personnel to address any issues related to WTT's execution of WTT's scope of work. Responsible for the equipment for movement of chemical drums, totes, and resins, as is reasonable. Provide all site utilities such as raw water, instrument quality air, potable water and power required for operation of the proposed equipment included in this scope of supply.

8.5. CONDITIONAL OFFERING

Client understands that this order confirmation has been issued based upon the information provided by Client and currently available to, WTT at the time of proposal issuance. Any changes or discrepancies in site conditions (including but not limited to system influent characteristics, changes in Environmental Health and Safety ("EH&S") conditions, and/or newly discovered EH&S concerns), Client financial standing, Client requirements, or any other relevant change, or discrepancy in, the factual basis upon which this proposal was created, may lead to changes in the offering, including but not limited to

changes in pricing, warranties, quoted specifications, or terms and conditions. WTT's offering in this proposal is conditioned upon a full WTT EH&S.

9. Appendix

9.1. Appendix A: Clarifications

- Pump MOC has been considered as per WTT standard practice.
- The Equipment in WTT scope will be procured as per WTT Standard Vendor List.
- WTT has not envisaged third party equipment inspection before dispatch.
- The payments received once could not be processed again for refund.
- WTT has considered instruments as per WTT standard practice
- Painting specifications of WTT supplied equipment is as per standard manufacturer painting specifications.

9.2. Appendix B: Acceptance

To ensure accurate and prompt order entry, product delivery, billing and accounts receivables processing, please ensure your Purchase Order contains the complete Client and order details.

Please communicate your PO through:

E-mail	venkat@wttint.com
Postal Mail: (Indian Office)	WTT INTERNATIONAL PVT. LTD. No. 3, College cross road Avarangadu, Tiruppur, TamilNadu, INDIA – 641602

Bank Account details:

Beneficiary Name : WTT INTERNATIONAL PVT. LTD.,
Bank Name : INDIAN BANK LTD
Branch Name : TIRUPUR MSME BRANCH, TIRUPUR, TAMILNADU.
Account Number OD : 6475173650,
IFSC Code : IDIB000I043

9.3. APPENDIX C: WARRANTY

The mechanical warranty is only applicable to equipment supplied by WTT. The mechanical warranty period on all equipment supplied, unless otherwise noted, is twelve (12) months from the date of installation or fourteen (14) months from equipment shipment, whichever occurs first. WTT's obligation under this warranty is to the repair or replace, of any device or part thereof, which shall prove to have been manufacturing defects.

This warranty excludes the diffuser membranes, electrical items, defects, failures, damages or performance limitations caused in whole or in part by normal wear & tear, power failures, surges, fires, floods, snow, ice, lightning, excessive heat or cold, highly corrosive environments, accidents, actions of third parties, or other events outside of WTT's control. Warranty period for the entire equipment including replaced or repaired parts will be limited to the unexpired portion of the total warranty period. Bought out components are guaranteed only to the extent of guarantees given to us by our suppliers.

WTT assumes no liability for any damage to equipment caused by inadequate storage or handling as per manufacturer's recommendations in supplied technical literature, or by defective or sub-standard workmanship or materials provided by Client or any other third party responsible for handling, storing or installing the equipment. Client undertakes to give immediate notice to WTT if goods or performance appear defective and to provide WTT with reasonable time and opportunity to make inspections and tests. If WTT is not at fault, Client shall pay WTT the costs and expenses of the inspections and tests.

Goods shall not be returned to WTT without WTT's permission. WTT will provide Client with a "Return Goods Authorization" (RGA) number to use for returned goods. All return costs associated with shipping and labor are not included in the mechanical warranty. WTT warrants, subject to the provisions herein after set forth, that after stable operation of the WTT system has been attained and operators have acquired reasonable skills, the Equipment supplied for this project will be capable of producing the results set forth in stage wise parameter table, provided that:

The Equipment is operated and maintained at all times in accordance with the WTT Operations and Maintenance manual, The Equipment is operated within the mixed liquor characteristics defined in Influent quality table of this section, WTT has, until performance of its obligation herein is met, reasonable access to the Equipment and the operational data

relating thereto, Client furnishes adequate and competent operating, supervisory and maintenance staff, and necessary laboratory facilities with test equipment and personnel, Client utilizes the services of WTT until its performance obligations are met, Client supplies all necessary raw materials and services of a quantity and of a quality specified by WTT, An adequate and continuous power supply is available that will enable operation of all required equipment.