12-Nov-25

To

M/s. REEDISHA GROUP,
GAZIPUR,
BANGLADESH.

[Proposal No: 12.Nov.2025/WTT-0948/BAN/NS-ZLD/30K/R0/TCP].

Dear Sir,

WTT International Private Limited (WTT) is pleased to provide **M/s. REEDISHA GROUP** with the Techno Commercial Proposal for supply of engineering & materials for **ZLD system of capacity 30 M^3/Day**. In developing this offer WTT worked with you in an effort to understand your project and business needs. The attached proposal outlines the solutions we feel will best meet these objectives.

We greatly appreciate your consideration of WTT for this project. Our measure of success is how well we deliver solutions that help our client to meet their critical business objectives. We hope to have the opportunity to demonstrate this with your good selves.

Yours Sincerely,

D. Venkatesh
Managing Director

S.NO	DESCRIPTION	PREPARED	APPROVED
1.	Techno commercial Proposal for – "ZLD system of capacity 30 M^3/Day".	MM - GET AR - AGM	DV - MD

CONFIDENTIALITY

All details, specifications, drawings, images, and all other information submitted by us are only intended to the person/organization to which it is addressed and contains proprietary, confidential and or privileged material. Any review, retransmission, dissemination, or other use of, or of taking action in reliance upon this information by person or entities other than the intended recipient is prohibited. All or part information contained in the document is solely intended to the person or entity addresses and sharing this document in part or in whole is prohibited.

WE FEEL DELIGHTED TO PRESENT OUR PATENTED SYSTEMS

Award for Excellence in Water Management

CII (Confederation of Indian Industry) *awarded*
WTT International *with the prestigious*

"Excellence in Water Management Award"

recognizing the advanced water treatment technologies
innovated by ***WTT International***
As a part of Industrial Water / Waste Management competition 2023

12.Nov.2025/WTT-0948/BAN/NS-ZLD/30K/R0/TCP

CONTENT

1. TECHNICAL AND ENGINEERING DETAILS 5
1.1. INFLUENT QUALITY 5
2. DESIGN BASIS 5
2.1. DESIGN SYSTEM CHOSEN 5
2.2. UTILITY CONSUMPTION DETAILS 6
3. MATERIAL OF CONSTRUCTION 6
4. SCOPE OF SUPPLY – EQUIPMENT, ENGINEERING & SERVICES 6
5. PRICING DETAIL 8
6. COMMERCIAL TERMS AND CONDITIONS 9
6.1. INVOICING AND PAYMENT TERMS 9
6.2. EQUIPMENT SHIPMENT 9
6.3. FORCE MAJEURE 9
6.4. PRICING NOTES 10
7. CLIENT SCOPE OF SUPPLY 10
7.1. SAFETY AND ENVIRONMENTAL 10
7.2. JOBSITE AND INSTALLATION REVIEW 11
7.3. START-UP AND COMMISSIONING 12
7.4. FACILITY MANAGEMENT 12
7.5. CONDITIONAL OFFERING 13
8. APPENDIX 13
8.1. APPENDIX A: ACCEPTANCE 13
8.2. APPENDIX B: CLARIFICATIONS 14

1. Technical and Engineering Details

1.1. Influent Quality

S.NO	PARAMETER	UNIT	EVAPORATOR INLET
1.	pH	--	6 – 7
2.	TDS	mg/L	30500 – 40500
3.	SULPHATE	mg/L	17500 – 18500
4.	CHLORIDE	mg/L	11000 – 12000
5.	HARDNESS	mg/L as $CaCO_3$	6200 – 6500

The design solution proposed is based on the values as presented in the table above at **Evaporator Inlet.** All concentrations refer to max concentrations to be used for the system's design. **Any change in the actual inlet parameters will have impact on Process Design, Engineering Design, Cost and Performance.**

2. Design Basis

2.1. Design System Chosen

S.NO	PROCESS	CAPACITY (M^3/DAY)	PROCESS
1.	DOUBLE STAGE FORCED CIRCULATION EVAPORATOR SYSTEM	30	PROPOSED TO RAISE CONCENTRATION OF RO REJECT WATER
2.	AGITATED THIN FILM DRYER (ATFD) SYSTEM		PROPOSED FOR ACHIEVING ZERO LIQUID DISCHARGE (ZLD) AND TO RECOVER MIXED SALT

NOTE: System capacities mentioned above are based on Evaporator influent flow Rate and the Actual capacities may vary.

2.2. UTILITY CONSUMPTION DETAILS

SYSTEM	STEAM	ABSORBED POWER (kWh)
DOUBLE STAGE FORCED CIRCULATION EVAPORATOR	700 Kg/hr @ 7 Kg(f)/cm^2	34.2
AGITATED THIN FILM DRYER SYSTEM	160 Kg/hr @ 7 Kg(f)/cm^2	9.6

3. MATERIAL OF CONSTRUCTION

S.NO	DESCRIPTION	MOC
1.	Tubes for Calandria	SA 213 TP 316
2.	Tubes for Surface Condenser	SA 213 TP 304
3.	Materials for Liquid Contact Parts	SA 240 GR 316
4.	Materials for Vapour Contact Parts	SA 240 GR 304

4. SCOPE OF SUPPLY – EQUIPMENT, ENGINEERING & SERVICES

WTT SCOPE OF SUPPLY	
S.NO	**DESCRIPTION**
1.	All Equipment Supply as per above Scope of Supply.
2.	Supply of Motor Cover.
3.	Instrument and its Automation.

CLIENT SCOPE OF SUPPLY	
S.NO	**DESCRIPTION**
1.	All civil works related with system, such as foundation of column, equipment and pumps, Necessary storage tank, if any other civil works not mentioned and related to the system.
2.	All statutory, legal and government formalities and permission for the erection and operation of the plant (PCB activities).
3.	Steam Boiler and its pipelines up to the system.
4.	Foundation Bolt, Nut and Its accessories.
5.	Unloading, storing of the equipment and safety at site.
6.	Supply of MS Structural, Skid and its Fabrication Work.
7.	Any Painting activities at Site.
8.	Supply of Electrical Cable and Cable tray and its accessories.
9.	Cooling Tower, Pump and its Pipelines.
10.	All Input and output Pipelines.
11.	Insulation of Equipment and Pipelines (If required)
12.	Necessary Electrical power supply and water supply for the equipment erection and fabrication at site.
13.	Necessary chemical and tools for trail run and commissioning of the system.
14.	Crane Charges for Erection at Site.
15.	Erection and Fabrication at Site.
16.	Lodging and Boarding of our engineers during E & C.
17.	If any other thing not mentioned other than the offer.

5. Pricing Detail

PRICE FOR PROPOSED SYSTEMS		
S.NO	**SYSTEM/EQUIPMENT**	**PRICE IN USD**
1.	**DOUBLE STAGE FORCED CIRCULATION EVAPORATOR WITH AGITATED THIN FILM DRYER (ATFD) SYSTEM as per above Specs – 30 KLD**	**$ 838,655**
2.	**ALLOWANCE PER ENGINEER FOR ONE DAY AT THE TIME OF ERECTION & COMMISSIONING SUPERVISION**	**$ 200**

- Pricing provided herein does not include any duties and taxes of destination country
- Transportation & Insurance – **Client Scope**
- TO and FRO Air tickets, local accommodation, VISA, Food and Local transport to the Project team of WTT will be done by **client**.
- Payment/commercial terms & conditions as per WTT's General Terms & Conditions of sale
- Price valid for 15 days from the date of proposal due to market volatility

6. Commercial Terms and Conditions

6.1. Invoicing and Payment Terms

The pricing quoted in this proposal is based on the following payment terms, in principally agreed.

(1) 40% advance along with order.

(2) 60% payment with 100% tax against Proforma invoice prior to dispatch or inspection at our factory.

Equipment shipment is contingent on receipt of earlier milestone payments.

6.2. Equipment Shipment

Client and WTT will arrange a kick off meeting after contract acceptance to develop firm shipment schedule. This estimated delivery schedule assumes no more than 1 week for Client review of submittal drawings. Any delays in Client approvals or requested changes may result in additional charges and/or a delay to the schedule.

Material supply for the proposed plants, partial Shipment starts from 4th months is expected from the date of receipt of clear purchase order. The delivery schedule excludes the months of August & December, the delivery schedule is subject to review and adjustment. In case of modifications to the volume of the supply after the emission of the order confirmation, WTT reserves the right to modify the delivery time and the agreed price.

6.3. Force Majeure

Please be advised that force majeure is applicable to the quotation provided. The unforeseen and uncontrollable events as defined in our terms and conditions, such as natural disasters, wars or pandemics & other events that prevent the parties from fulfilling their contractual commitments have occurred, impacting our ability to honor the terms outlined in this quotation. We will diligently review the situation and promptly communicate any necessary adjustments or potential delays in fulfilling the quoted services or products in compliance with the force majeure provisions outlined in our agreement.

6.4. PRICING NOTES

All prices quoted are in **USD**. Any applicable tax of destination country is not included. Client will pay all applicable Local, State / Provincial, or Federal taxes & Duties. WTT may manufacture and source the Equipment and any part thereof globally in the country or countries of its choosing, provided that the Equipment complies with all of the requirements specified in this Agreement.

The Equipment delivery date, start date, and date of commencement of operations are to be negotiated. Title and risk of loss will transfer upon delivery in accordance with the INCOTERMS 2010. Commercial Terms and Conditions shall be in accordance with WTT's General Terms and Conditions of Sale as included in Appendix.

7. CLIENT SCOPE OF SUPPLY

7.1. SAFETY AND ENVIRONMENTAL

First aid, emergency medical response, eyewash & safety showers in the water treatment area. Chemical spill response, security & fire protection systems as per local codes. Environmental use and discharge permits for all chemicals at Client facility either listed in this document or proposed for use at a later date. Any special permits required for WTT's or Client employees to perform work related to the water treatment system at the facility. All site testing, including soil, ground and surface water, and air emissions, etc. Disposal of all solid & liquid waste from WTT's system including waste materials generated during construction, startup and operation.

Provide appropriate protection of the environment & local community, the health and safety of all workers and visitors at the site and the security of the facility. Provide safety related equipment & services such as site security, fire systems, lifting equipment and its operation, fall protection, adequate floor grating, ventilation, and safe access to equipment & electrical systems areas.

Equipment and trained support personnel for any confined space entry required during equipment installation/startup/commissioning/servicing. For permit-required confined space entry, a qualified rescue team on stand-by and available to respond within 4 minutes of an emergency.

Client will identify and inform WTT's personnel of any hazards present in the work place that could impact the delivery of WTT's scope of supply and agrees to work with WTT to remove, monitor, and control the hazards to a practical level. Client will provide training to WTT's personnel on all relevant & standard company operating procedures and practices for performing work on site.

7.2. JOBSITE AND INSTALLATION REVIEW

Review of WTT's supplied equipment drawings and specifications. All easements, licenses and permits required by governmental or regulatory authorities in Connection with the supply, erection and operation of the system.

Overall plant design, detail drawings of all termination points where WTT's equipment or Materials tie into equipment or materials supplied by others Stamping, signing or Sealing General drawings as per State, or local regulations or codes. All applicable civil design and works, including any building, site preparation, grading, excavations, foundations and trenches and accessories.

All electrical Labor and supplies leading up to jobsite including fittings, conduit, supports, cable trays, wire and hardware, air-conditioning of panels required to appropriately ground / earth the equipment as required for installation and ongoing operations.

All mechanical Labor and supplies leading up to jobsite including interconnecting piping, heat tracing (if required), fittings, conduit, pipe supports, and hardware as required for installation and ongoing operations. All instrumentation and automatic pneumatic valves including but not limited to; air/sample line tubing, fittings, conduit, supports, isolating valves as required for installation and ongoing operations. Loading, unloading and transportation of equipment, materials required for WTT to perform duties outlined in WTT's Scope of Supply to the jobsite and/or warehouse.

Client will provide all access structures (scaffolding), mechanical lifting equipment (cranes, forklifts, scissor lifts, etc.), suitable site/shelter for placement of the proposed equipment, either inside appropriate housing, or outdoors.

Precaution: electrical equipment including the PLC may require air-conditioned rooms to prevent overheating of sensitive electronic equipment depending on climatic conditions. Bulk chemical storage and tanks, including secondary containment in accordance with local codes. Client will receive, off-load, log, and store all chemical and materials in accordance with Manufacturer's recommendation that are shipped. Compressed instrument air for pneumatic valves instruments and ejector system Equipment anchor bolts, Laboratory services, operating and maintenance personnel during equipment checkout, start-up and operation. Any on-site painting or touch-up painting of equipment supplied. Disposal of any Preservative.

For erection, WTT will ship the accessories such as pipes, bolts, nuts, screws, cables, valves any other equipment or devices in excess quantities than required. This is in order to avoid shortages during the assembly due to damage or any other cause as it is difficult to procure the accessories locally. It is notified that all the shipped accessories during assembly and the excess accessories after commissioning are always remain the properties of WTT. WTT has the authority to retake the same at any period of time, even before and after commissioning. It is client's responsibility to preserve the above-mentioned items till WTT takes back the same.

7.3. START-UP AND COMMISSIONING

Installation & removal of temporary screens on all process lines Flushing and disinfection of all piping and tanks (including process equipment tanks) and verification of removal of all residual debris from construction. Alignments & required materials for rotating equipment MEG testing of all field motor power wiring (as required). Continuity checks for all electrical field wiring as per Installation Checklist, Hydro-testing of all field installed piping. Supply raw materials, oil/lubricants chemicals and utilities during start-up and operation. Electrical & Mechanical support labor for commissioning activities, loading of membranes, stacks, modules, etc.

7.4. FACILITY MANAGEMENT

Client will provide such warehouse storage space and facilities, as are available at the site, and are reasonably appropriate to store parts, consumables, tools, etc. in accordance with manufacturer's recommendations. Such warehouse storage space will be a segregated area, secured and protected from adverse climate as may reasonably be required. The

storage area shall be facilitated with 24 hours lock & key with security and Client will be responsible for risk of loss of WTT's parts while in storage at the site. Client will maintain WTT's parts stored at the site free & clear of any and all liens of Client and lenders, bondholders, contractors & other creditors of any nature.

Client will afford WTT's personnel free access and egress of the facility for all authorized work. Provide workshop facilities/area with roof and stabilized power supply, as is reasonably appropriate to carry out machining/fabrication works.

Provide adequate illumination and emergency lighting for all areas in which the WTT will be executing the scope of supply. Identify a Client project contact person to be available to WTT's personnel to address any issues related to WTT's execution of WTT's scope of work. Responsible for the equipment for movement of chemical drums, totes, and resins, as is reasonable. Provide all site utilities such as raw water, instrument quality air, potable water and power required for operation of the proposed equipment included in this scope of supply.

7.5. CONDITIONAL OFFERING

Client understands that this order confirmation has been issued based upon the information provided by Client and currently available to, WTT at the time of proposal issuance. Any changes or discrepancies in site conditions (including but not limited to system influent characteristics, changes in Environmental Health and Safety ("EH&S") conditions, and/or newly discovered EH&S concerns), Client financial standing, Client requirements, or any other relevant change, or discrepancy in, the factual basis upon which this proposal was created, may lead to changes in the offering, including but not limited to changes in pricing, warranties, quoted specifications, or terms and conditions. WTT's offering in this proposal is conditioned upon a full WTT EH&S.

8. APPENDIX

8.1. APPENDIX A: ACCEPTANCE

To ensure accurate and prompt order entry, product delivery, billing and accounts receivables processing, please ensure your Purchase Order contains the complete Client and order details.

Please communicate your PO through:

E-mail	venkat@wttint.com
Postal Mail: (Indian Office)	WTT INTERNATIONAL PVT. LTD. No. 3, College cross road Avarangadu, Tiruppur, TamilNadu, INDIA – 641602

Bank Account details:

Beneficiary Name : WTT INTERNATIONAL PVT. LTD.,

Bank Name : INDIAN BANK LTD

Branch Name : TIRUPUR MSME BRANCH, TIRUPUR, TAMILNADU.

Account Number OD : 6475173650,

IFSC Code : IDIB000I043

8.2. APPENDIX B: CLARIFICATIONS

- Pump MOC has been considered as per WTT standard practice.
- The Equipment in WTT scope will be procured as per WTT Standard Vendor List.
- WTT has not envisaged third party equipment inspection before dispatch.
- The payments received once could not be processed again for refund.
- WTT has considered instruments as per WTT standard practice
- Painting specifications of WTT supplied equipment is as per standard manufacturer painting specifications.